



NOTES:

1. FOURTY EIGHT (48) HOURS NOTICE IS TO BE GIVEN PRIOR TO THE PLACING OF CONCRETE TO ALLOW FOR INSPECTION BY COUNCIL'S OFFICER.
2. CONCRETE TO BE OF 20 MPa COMPRESSIVE STRENGTH (F_c) AT 28 DAYS.
3. GRATES TO BE HINGED 'WELDLCK' DISHED CROSSING G.G.7862 SET PARALLEL TO EDGE OF GUTTER.
4. PIPE TRENCHES BACKFILLED WITH SAND SHALL HAVE 3 m OF SUBSOIL DRAIN PIPE IN THE BOTTOM OF THE TRENCH AND DRAINING INTO THE PIT.

Fig. D5.Misc.1



SCALE 1:1 N.T.S.

SUBDIVISION
CODE

CITY OF SHOALHAVEN
STANDARD DISHED
GUTTER INLET PIT

ENGINEERING WORKS
MANAGER

DRAWN	C. FIESELER
CHECKED	J. BLOH
PLAN REF.	263701
DATE	04. MAY 1984