

Indicative Cost Plan Nowra Car Park

Azeem Bhola Cost Manager

Turner & Townsend Level 1, Empire Chambers 1 University Avenue Canberra City ACT 2601

t: +61 (0)2 6245 1000

e: azeem.bhola@turntown.com
w: turnerandtownsend.com

Nowra Car Park





CONTENTS

1	INTRODUCTION	1
2	INTENT	1
3	INFORMATION USED	1
4	ASSUMPTIONS	2
5	EXCLUSIONS	3
6	APPENDIX A - INDICATIVE COST PLAN	4

Rev	Originator	Approved	Date
0	Azeem Bhola	Matt Figgis	07.06.2012

© Turner & Townsend Cost Management. All rights reserved June 7th. This document is expressly provided to and solely for the use of GHD and their client and must not be quoted from, referred to, used by or distributed to any other party without the prior consent of Turner & Townsend Cost Management who accept no liability of whatsoever nature for any use by any other party.

F:\CBR\PROJECTS\CAXXXX - NOWRA CAR PARK\2000 COSTPLAN\2200 COST PLANS\2210 INDICATIVE CP\2211 COST PLAN FILES\NOWRA CAR PARK.DOC

1 Introduction

Turner & Townsend have been engaged by GHD Architects to provide an indicative estimate for the construction of a car park at Worrigee Street .

2 Intent

The intent of this report is to advise of the likely cost of construction of the car park with three alternative options varying number of floors and extent of cladding .

The budget should be read in conjunction with the drawings and information as outlined in this report.

Based on all the drawings and information provided by GHD $\,$ our Estimate, excluding GST :

- 1. Car park Constructio Grd to Level 4 -\$11.1m
- 2. Car park Constructio Grd to Level 4 without cladding -\$9.9m
- 3. Car park Constructio Grd to Level 3 with cladding -\$8.7m
- 4. Car park Constructio Grd to Level 3 without cladding -\$7.7m

3 Information Used

The following drawings / information have been used to prepare this report:

Drawing /Description	Date Received
Site Plan (SK 110)	6.06.2012
Typical Layout (SK 120)	6.06.2012
Building Sections (SK 140)an	6.06.2012
Elevations East /West (SK 151)	6.06.2012

Elevations North /South (SK 150)	6.06.2012
3D Isometric View (SK 260)	6.06.2012

4 Assumptions

- Foundation footings are of size 3500x3500x900mm
- Broom Finish to concrete Slabs on all floors
- All stairs including perimeter wall to stairwell be cast in concrete.
- Grd floor slab is to be 120mm
- Suspended slab is 200mm thk
- Beams for slabs are 2000mm wide and 400mm deep
- Sheet piling is excluded for shoring level change of three meters at ground floor
- Reinforcement ratios for Foundation footing is 100Kg/m3, Suspended Slab is 250kg/m3 and for Columns is 200kg/m3.
- Curtain Walling is Lightweight louvered perforated metal panels .
- Extent of earthworks as per provided quantity by 1350m3.
- Power and Lighting costs as per provided by GHD
- All rates as per current market rate .
- No abnormal ground conditions .
- No diversion of existing services crossing or abutting the site .
- Incoming mains services are sufficient for the power requirements of the car park
- No demolition Works
 - Preliminaries and OH&P 10%
 - Contingency 5%

5 Exclusions

- Fire Protection
- Smoke Detectors
- Sanitary Plumbing
- Air Conditioning
- Bored Pile foundation
- Demolition
- Removal of contaminated land (if any)
- Security costs, CCTV .
- Out of hours work
- Professional fees / Certification costs
- Scope not expressly described in the cost plan backup
- Escalation beyond 3Q12
- GST



Appendix A – Indicative Cost Plan Options 1-4 below .

Trade Summary

Project: Car Park Construction Details: Nowra Car PArk

Building: Nowra Car Park

Code	Description	Quantity	Unit	Rate	Total
	Substructure				1,215,816
	Columns				287,340
	Suspended Slab				5,797,78
	Staircases				267,830
	Ramps Grd to Level 4				148,58
	Perimeter Crash Barrier				229,000
	External Wall Cladding				1,080,60
	Doors				14,400
	Wall Finishes				5,550
	Floor Finishes				208,31
	Fitments				199,20
	Electric Lighting				174,60
	Power Supply				40,00
	External Concrete Path				52,50
	Sub Total				9,721,51
	Preliminaries 10%				972,15
	Contingencies 5%				486,07
	Total				11,179,73

Trade Detail

Project: Car Park Construction

Details: Nowra Car PArk

Building: Nowra Car Park

Code	Des	cription	Quantity	Unit	Rate	Subtotal
Subst	ructure					
	Grd Floor Slab					
	Bulk Excavation and Cart away		1,350	m3	60.00	81,000.00
	Level Compact Grd Floor		4,481	m2	15.00	67,219
	Excavation for footings		916	m3	151.00	138,316
	Reinforcement to Footings		92	t	2,800.00	257,600
	Concrete to Footings		916	m3	286.00	261,976
	Sand Bed		4,481	m2	10.00	44,813
	Water Proof Membrane		4,481	m2	15.00	67,219
	Expansion Joints		360	m	20.00	7,200
	Mesh Reinforcement to Slab		4,481	m2	20.00	89,625
	Formwork to Edge of slab		292	m	43.00	12,561
	Concrete to Slab		538	m3	300.00	161,400
	Finish and Cure Slab		4,481	m2	6.00	26,888

Substructure

Columns

Columns Grd Floor (3.0)				
Formwork to rectangular columns 600x250.	271	m2	120.00	32,520
Reinforcement in Columns (200kg/m3)	5	t	2,800.00	14,000
Concrete in Columns	24	m3	282.00	6,768
Columns Grd Floor (2.8)				
Formwork to rectangular columns 600x250	143	m2	120.00	17,160
Reinforcement in Columns (200kg/m3)	3	t	2,800.00	8,400
Concrete in Columns	13	m3	282.00	3,666
Columns Half Slab (2.8)				
Formwork to rectangular columns 600x250	253	m2	120.00	30,360
Reinforcement in Columns (200kg/m3)	5	t	2,800.00	14,000
Concrete in Columns	23	m3	282.00	6,486
Columns Level 2 (2.8)				
Formwork to rectangular columns 600x250	396	m2	120.00	47,520
Reinforcement in Columns (200kg/m3)	7	t	2,800.00	19,600
Concrete in Columns	35	m3	282.00	9,870
Columns Level 3 (2.8)				
Formwork to rectangular columns 600x250	396	m2	120.00	47,520
Reinforcement in Columns (200kg/m3)	7	t	2,800.00	19,600
Concrete in Columns	35	m3	282.00	9,870

Trade Detail

Project: Car Park Construction

Details: Nowra Car PArk

Building: Nowra Car Park

	Code	Description	Quantity	Unit	Rate	Subtotal
--	------	-------------	----------	------	------	----------

Columns

Suspended Slab

Columns

pe	nded Slab				
	Suspended Half Slab Level 1				
	Formwork to soffit of suspended slab and beams	2,580	m2	100.00	257,967
	Formwork to edge of slab perimeter	292	m	43.00	12,561
	Reinforcement in slabs and beams (250kg/m3)	209	t	2,800.00	585,200
	Concrete to slab and beams	836	m3	260.00	217,360
	Finish and cure slab	2,580	m2	10.00	25,797
	Suspended Slab Level 2				
	Formwork to soffit of slab and beams	4,481	m2	100.00	448,126
	Formwork face of beam and edge of slab	292	m	43.00	12,561
	Reinforcement in slabs and beams (250kg/m3)	276	t	2,800.00	773,500
	Concrete to slab and beams	1,105		260.00	287,300
	Finish and cure slab	4,481		10.00	44,813
	Suspended Slab Level 3				
	Formwork to soffit of slab and beams	4,481	m2	100.00	448,126
	Formwork face of beam and edge of slab	292	m	43.00	12,561
	Reinforcement in slabs and beams (250kg/m3)	276	t	2,800.00	773,500
	Concrete to slab and beams	1,105		260.00	287,300
	Finish and cure slab	4,481		10.00	44,813
	Suspended Slab Level 4				
	Formwork to soffit of slab and beams	4,481	m2	100.00	448,126
	Formwork face of beam and edge of slab	292	m	43.00	12,561
	Reinforcement in slabs and beams (250kg/m3)	276	t	2,800.00	773,500
	Concrete to slab and beams	1,105		260.00	287,300
	Finish and cure slab	4,481		10.00	44,813

Suspended Slab

Staircases

Formwork to stairs /perimeter wall	1,039	m2	100.00	103,900
Concrete to Stairs /perimeter wall	224	m3	300.00	67,200
Reinforcement to staircase	26	t	2,800.00	74,010
Balustrades	60	m	162.00	9,720

(Continued)

Trade Detail

Project: Car Park Co Building: Nowra Car I		Details: Nowra Car	PArk		
Code	Description	Quantity	Unit	Rate	Subtotal
Staircases	·	·			(Continued)
Aluminium Canopy to stair	well roof .	52	m2	250.00	13,000
Staircases				I	
Ramps Grd to Level 4					
Ramp Grd to Level 4					
Formwork to ramps		478	m2	100.00	47,800
Reinforcement to ramps		24	t	2,800.00	67,200
Concrete to ramps		96	m3	300.00	28,800
Finish and cure ramps		478	m2	10.00	4,780
Ramps Grd to Level 4		·			
Perimeter Crash Barrier					
Crash Barrier		1,145	m	200.00	229,000
Perimeter Crash Barrier		1,140	l	200.00	220,000
External Wall Cladding					
Curtail walling louvered pe	forated metal panels	2,161	m2	500.00	1,080,600
External Wall Cladding		I			
Doors					
Solid core doors inclusive	of hardware for eatrances into srairwell	18	no	800.00	14,400
Doors				•	
Wall Finishes					
Paint to Stairwell walls		370	m2	15.00	5,550
Wall Finishes		•			
Floor Finishes					
Line markings		16,024	m2	5.00	80,120
Sealer and paint to concret	e floor	16,024	m2	8.00	128,192
Floor Finishes					
Fitments					
Wheel Stops		512	no	350.00	179,200
Sundry carpark fitments an	d signage	1	item	20,000.00	20,000
Fitments					
Electric Lighting					
Top floor lighting		1	item	75,000.00	75,000
Lighting Grd , Level 2, Level	el 3	3	item	28,000.00	84,000
Lighting Half Suspended F	loor	1	item	15,600.00	15,600
Electric Lighting					
Power Supply		Т		<u> </u>	
Power Supply and distribut	ion	1	item	40,000.00	40,000
Power Supply					
External Concrete Path					

CostX Turner & Townsend Page 3 of 4

Trade Detail

Project: Car Park Construction Building: Nowra Car Park Details:		Is: Nowra Car PArk				
Code	Description		Quantity	Unit	Rate	Subtotal
Extern	External Concrete Path (Continu					(Continued)
	External conc Path (1m wide)		210	m	250.00	52,500

External Concrete Path

Trade Summary

Project: Car Park Construction

Details: Nowra Car PArk -W/O Cladding Option 2

Building: Nowra Car Park

Code	Description	Quantity	Unit	Rate	Total
	Substructure				1,215,81
	Columns				287,34
	Suspended Slab				5,797,78
	Staircases				267,83
	Ramps Grd to Level 4				148,58
	Perimeter Crash Barrier				229,00
	External Wall Cladding (Excluded)				
	Doors				14,40
	Wall Finishes				5,55
	Floor Finishes				208,31
	Fitments				199,20
	Electric Lighting				174,60
	Power Supply				40,00
	External Concrete Path				52,50
	Sub Total				8,640,91
	Preliminaries 10%				864,09
	Contingencies 5%				432,04
	Total				9,937,04

Trade Detail

Project: Car Park Construction

Details: Nowra Car PArk -W/O Cladding Option 2

Building: Nowra Car Park

Code	Description	Quantity	Unit	Rate	Subtotal
Substructur	re				
Grd	Floor Slab				
Bulk	Excavation and Cart away	1,350	m3	60.00	81,000.00
Leve	el Compact Grd Floor	4,481	m2	15.00	67,219
Exca	avation for footings	916	m3	151.00	138,316
Rein	nforcement to Footings	92	t	2,800.00	257,600
Cond	crete to Footings	916	m3	286.00	261,976
Sand	d Bed	4,481	m2	10.00	44,813
Wate	er Proof Membrane	4,481	m2	15.00	67,219
Ехра	ansion Joints	360	m	20.00	7,200
Mesl	sh Reinforcement to Slab	4,481	m2	20.00	89,625
Form	nwork to Edge of slab	292	m	43.00	12,561
Cond	crete to Slab	538	m3	300.00	161,400
Finis	sh and Cure Slab	4,481	m2	6.00	26,888

Substructure

Columns

Columns Grd Floor (3.0)				
Formwork to rectangular columns 600x250.	271	m2	120.00	32,520
Reinforcement in Columns (200kg/m3)	5	t	2,800.00	14,000
Concrete in Columns	24	m3	282.00	6,768
Columns Grd Floor (2.8)				
Formwork to rectangular columns 600x250	143	m2	120.00	17,160
Reinforcement in Columns (200kg/m3)	3	t	2,800.00	8,400
Concrete in Columns	13	m3	282.00	3,666
Columns Half Slab (2.8)				
Formwork to rectangular columns 600x250	253	m2	120.00	30,360
Reinforcement in Columns (200kg/m3)	5	t	2,800.00	14,000
Concrete in Columns	23	m3	282.00	6,486
Columns Level 2 (2.8)				
Formwork to rectangular columns 600x250	396	m2	120.00	47,520
Reinforcement in Columns (200kg/m3)	7	t	2,800.00	19,600
Concrete in Columns	35	m3	282.00	9,870
Columns Level 3 (2.8)				
Formwork to rectangular columns 600x250	396	m2	120.00	47,520
Reinforcement in Columns (200kg/m3)	7	t	2,800.00	19,600
Concrete in Columns	35	m3	282.00	9,870

Trade Detail

Project: Car Park Construction
Building: Nowra Car Park

Description

Details: Nowra Car Park -W/O Cladding Option 2

Quantity Unit Rate Subtotal

Columns (Continued)

Columns

Suspended Slab

pe	nded Slab					_
	Suspended Half Slab Level 1					
	Formwork to soffit of suspended slab and beams	2,580	m2	100.00	257,967	
	Formwork to edge of slab perimeter	292	m	43.00	12,561	
	Reinforcement in slabs and beams (250kg/m3)	209	t	2,800.00	585,200	
	Concrete to slab and beams	836	m3	260.00	217,360	
	Finish and cure slab	2,580	m2	10.00	25,797	
	Suspended Slab Level 2					
	Formwork to soffit of slab and beams	4,481	m2	100.00	448,126	
	Formwork face of beam and edge of slab	292	m	43.00	12,561	
	Reinforcement in slabs and beams (250kg/m3)	276	t	2,800.00	773,500	
	Concrete to slab and beams	1,105		260.00	287,300	
	Finish and cure slab	4,481		10.00	44,813	
	Suspended Slab Level 3					
	Formwork to soffit of slab and beams	4,481	m2	100.00	448,126	
	Formwork face of beam and edge of slab	292	m	43.00	12,561	
	Reinforcement in slabs and beams (250kg/m3)	276	t	2,800.00	773,500	
	Concrete to slab and beams	1,105		260.00	287,300	
	Finish and cure slab	4,481		10.00	44,813	
	Suspended Slab Level 4					
	Formwork to soffit of slab and beams	4,481	m2	100.00	448,126	
	Formwork face of beam and edge of slab	292	m	43.00	12,561	
	Reinforcement in slabs and beams (250kg/m3)	276	t	2,800.00	773,500	
	Concrete to slab and beams	1,105		260.00	287,300	
	Finish and cure slab	4,481		10.00	44,813	

Suspended Slab

Staircases

Formwork to stairs /perimeter wall	1,039	m2	100.00	103,900
Concrete to Stairs /perimeter wall	224	m3	300.00	67,200
Reinforcement to staircase	26	t	2,800.00	74,010
Balustrades	60	m	162.00	9,720

Trade Detail

Project: Car Park Construction Building: Nowra Car Park	Details: Nowra Ca	W/O Cladding	Cladding Option 2	
Code Description	Quantity	Unit	Rate	Subtotal
Staircases				(Continued
Aluminium Canopy to stairwell roof .	52	m2	250.00	13,000
Staircases	•	•		
Ramps Grd to Level 4				
Ramp Grd to Level 4				
Formwork to ramps	478	m2	100.00	47,800
Reinforcement to ramps	24	t	2,800.00	67,200
Concrete to ramps	96	m3	300.00	28,800
Finish and cure ramps	478	m2	10.00	4,780
Ramps Grd to Level 4				
Perimeter Crash Barrier		1		
	1.115		000.00	000 000
Crash Barrier	1,145	m	200.00	229,000
Perimeter Crash Barrier Doors				
Solid core doors inclusive of hardware for eatrances into srairwell	18	no	800.00	14,400
Doors	10	110	800.00	14,400
Wall Finishes				
Paint to Liftwell walls	370	m2	15.00	5,550
Wall Finishes		11112	10.00	
Floor Finishes				
Line markings	16,024	m2	5.00	80,120
Sealer and paint to concrete floor	16,024	1	8.00	128,192
Floor Finishes		1	5.00	,
Fitments				
Wheel Stops	512	no	350.00	179,200
Sundry carpark fitments and signage	1	item	20,000.00	20,000
Fitments			1	
Electric Lighting				
Top floor lighting	1	item	75,000.00	75,000
Lighting Grd , Level 2, Level 3	3	item	28,000.00	84,000
Lighting Half Suspended Floor	1	item	15,600.00	15,600
Electric Lighting	•	•	. l	
Power Supply				
Power Supply and distribution	1	item	40,000.00	40,000
Power Supply	•	•		
External Concrete Path				
External conc Path (1m wide)	210	m	250.00	52,500
External Concrete Path	<u> </u>	•		

CostX Turner & Townsend Page 3 of 3 8/06/2012 9:41:33 AM

Trade Summary

Details: Nowra Car PArk -3 levels with cladding Option 3 Project: Car Park Construction

Building: Nowra Car Park

Code	Description	Quantity	Unit	Rate	Total
	Substructure				1,215,816
	Columns				210,350
	Suspended Slab				4,231,483
	Staircases				226,115
	Ramps Grd to Level 3				111,490
	Perimeter Crash Barrier				170,600
	External Wall Cladding				880,000
	Doors				9,600
	Wall Finishes				4,45
	Floor Finishes				150,059
	Fitments				147,75
	Electric Lighting				146,600
	Power Supply				40,000
	External Concrete Path				52,500
	Sub Total				7,596,818
	Preliminaries 10%				759,68
	Contingencies 5%				379,84
	Total				8,736,34

Trade Detail

	Project: Car Park Construction Building: Nowra Car Park	Details:	ils: Nowra Car PArk -3 levels with cladding Option 3				
Code	Description		Quantity	Unit	Rate	Subtotal	
Substr	ucture						
	Grd Floor Slab						
	Bulk Excavation and Cart away		1,350	m3	60.00	81,000.00	
	Level Compact Grd Floor		4,481	m2	15.00	67,219	
	Excavation for footings		916	m3	151.00	138,316	
	Reinforcement to Footings		92	t	2,800.00	257,600	
	Concrete to Footings		916	m3	286.00	261,976	
	Sand Bed		4,481	m2	10.00	44,813	
	Water Proof Membrane		4,481	m2	15.00	67,219	
	Expansion Joints		360	m	20.00	7,200	
	Mesh Reinforcement to Slab		4,481	m2	20.00	89,625	
	Formwork to Edge of slab		292	m	43.00	12,561	
	Concrete to Slab		538	m3	300.00	161,400	
	Finish and Cure Slab		4,481	m2	6.00	26,888	
	Substructure						
Colum	ns						
	Columns Grd Floor (3.0)						
	Formwork to rectangular columns 600x250.		271	m2	120.00	32,520	
	Reinforcement in Columns (200kg/m3)		5	t	2,800.00	14,000	
	Concrete in Columns		24	m3	282.00	6,768	
	Columns Grd Floor (2.8)						
	Formwork to rectangular columns 600x250		143	m2	120.00	17,160	
	Reinforcement in Columns (200kg/m3)		3	t	2,800.00	8,400	
	Concrete in Columns		13	m3	282.00	3,666	
	Columns Half Slab (2.8)						
	Formwork to rectangular columns 600x250		253	m2	120.00	30,360	
	Reinforcement in Columns (200kg/m3)		5	t	2,800.00	14,000	
	Concrete in Columns		23	m3	282.00	6,486	
	Columns Level 2 (2.8)						
	Formwork to rectangular columns 600x250		396	m2	120.00	47,520	
	Reinforcement in Columns (200kg/m3)		7	t	2,800.00	19,600	
	Concrete in Columns		35	m3	282.00	9,870	
	Columns	<u>'</u>			· ·		
Susper	nded Slab						
	Suspended Half Slab Level 1						
	Formwork to soffit of suspended slab and beams		2,580	m2	100.00	257,967	
	Formwork to edge of slab perimeter		292	m	43.00	12,561	

Project: Car Park Construction

Trade Detail

Details: Nowra Car PArk -3 levels with cladding

Building: Nowra Car Park	Option 3			
Code Description	Quantity	Unit	Rate	Subtotal
Suspended Slab				(Continued)
Reinforcement in slabs and beams (250kg/m3)	209	t	2,800.00	585,200
Concrete to slab and beams	836	m3	260.00	217,360
Finish and cure slab	2,580	m2	10.00	25,797
Suspended Slab Level 2				
Formwork to soffit of slab and beams	4,481	m2	100.00	448,126
Formwork face of beam and edge of slab	292	m	43.00	12,561
Reinforcement in slabs and beams (250kg/m3)	276	t	2,800.00	773,500
Concrete to slab and beams	1,105		260.00	287,300
Finish and cure slab	4,481		10.00	44,813
Suspended Slab Level 3				
Formwork to soffit of slab and beams	4,481	m2	100.00	448,126
Formwork face of beam and edge of slab	292	m	43.00	12,561
Reinforcement in slabs and beams (250kg/m3)	276	t	2,800.00	773,500
Concrete to slab and beams	1,105		260.00	287,300
Finish and cure slab	4,481		10.00	44,813
Suspended Slab				
Staircases	T		Т Т	
Formwork to stairs /perimeter wall	865	m2	100.00	86,500
Concrete to Stairs /perimeter wall	188	m3	300.00	56,400
Reinforcement to staircase	22	t	2,800.00	62,115
Balustrades	50	m	162.00	8,100
Aluminium Canopy to stairwell roof .	52	m2	250.00	13,000
Staircases Ramps Grd to Level 3				
Ramp Grd to Level 4				
Formwork to ramps	359	m2	100.00	35,900
Reinforcement to ramps	18		2,800.00	50,400
Concrete to ramps	72		300.00	21,600
Finish and cure ramps	359		10.00	3,590
Ramps Grd to Level 3	1 555	L=	1	
Perimeter Crash Barrier				
Crash Barrier	853	m	200.00	170,600
Perimeter Crash Barrier				
External Wall Cladding				

CostX Turner & Townsend Page 2 of 3

Trade Detail

Project: Car Park Construction Building: Nowra Car Park	Deta	Is: Nowra Car PArk -3 levels with cladd Option 3			dding
Code Descrip	ition	Quantity	Unit	Rate	Subtotal
External Wall Cladding					(Continue
Curtail walling louvered perforated aluminium p	vanels	1,760	m2	500.00	880,000
External Wall Cladding					
Doors					
Solid core doors inclusive of hardware for eatra	inces into srairwell	12	no	800.00	9,60
Doors					
Wall Finishes					
Paint to Liftwell walls		297	m2	15.00	4,45
Wall Finishes					
Floor Finishes					
Line markings		11,543	m2	5.00	57,71
Sealer and paint to concrete floor		11,543	m2	8.00	92,34
Floor Finishes					
Fitments					
Wheel Stops		365	no	350.00	127,75
Sundry carpark fitments and signage		1	item	20,000.00	20,00
Fitments					
Electric Lighting					
Top floor lighting		1	item	75,000.00	75,00
Lighting Grd , Level 2, Level 3		2	item	28,000.00	56,00
Lighting Half Suspended Floor		1	item	15,600.00	15,60
Electric Lighting		•	•		
Power Supply					
Power Supply and distribution		1	item	40,000.00	40,00
Power Supply		•			
External Concrete Path					
External conc Path (1m wide)		210	m	250.00	52,50

External Concrete Path

CostX Turner & Townsend Page 3 of 3

Trade Summary

Details: Nowra Car PArk -3 levels w/o cladding Option 4 Project: Car Park Construction

Building: Nowra Car Park

Description	Quantity	Unit	Rate	Total
Substructure				1,215,810
Columns				210,35
Suspended Slab (3 levels Only)				4,231,48
Staircases				226,11
Ramps Grd to Level 3				111,49
Perimeter Crash Barrier				170,60
External Wall Cladding (Excluded)				
Doors				9,60
Wall Finishes				4,45
Floor Finishes				150,05
Fitments				147,75
Electric Lighting				146,60
Power Supply				40,00
External Concrete Path				52,50
Sub Total				6,716,81
Preliminaries 10%				671,68
				335,84
Total				7,724,34
	ı			
	Substructure Columns Suspended Slab (3 levels Only) Staircases Ramps Grd to Level 3 Perimeter Crash Barrier External Wall Cladding (Excluded) Doors Wall Finishes Floor Finishes Fitments Electric Lighting Power Supply External Concrete Path	Substructure Columns Suspended Slab (3 levels Only) Staircases Ramps Grd to Level 3 Perimeter Crash Barrier External Wall Cladding (Excluded) Doors Wall Finishes Floor Finishes Fitments Electric Lighting Power Supply External Concrete Path Sub Total Preliminaries 10% Contingencies 5%	Substructure Columns Suspended Slab (3 levels Only) Staircases Ramps Grd to Level 3 Perimeter Crash Barrier External Wall Cladding (Excluded) Doors Wall Finishes Floor Finishes Fitments Electric Lighting Power Supply External Concrete Path Sub Total Preliminaries 10% Contingencies 5%	Substructure Columns Suspended Slab (3 levels Only) Staircases Ramps Grd to Level 3 Perimeter Crash Barrier External Wall Cladding (Excluded) Doors Wall Finishes Floor Finishes Fitments Electric Lighting Power Supply External Concrete Path Sub Total Preliminaries 10% Contingencies 5%

Trade Detail

	Project: Car Park Construction Building: Nowra Car Park	Details: Nowra Car PArk -3 levels w/o cladding Option 4				
Code	Description		Quantity	Unit	Rate	Subtotal
Substr	ucture					
	Grd Floor Slab					
	Bulk Excavation and Cart away		1,350	m3	60.00	81,000.00
	Level Compact Grd Floor		4,481	m2	15.00	67,219
	Excavation for footings		916	m3	151.00	138,316
	Reinforcement to Footings		92	t	2,800.00	257,600
	Concrete to Footings		916	m3	286.00	261,976
	Sand Bed		4,481	m2	10.00	44,813
	Water Proof Membrane		4,481	m2	15.00	67,219
	Expansion Joints		360	m	20.00	7,200
	Mesh Reinforcement to Slab		4,481	m2	20.00	89,625
	Formwork to Edge of slab		292	m	43.00	12,561
	Concrete to Slab		538	m3	300.00	161,400
	Finish and Cure Slab		4,481	m2	6.00	26,888
	Substructure					
Colum	ns					
	Columns Grd Floor (3.0)					
	Formwork to rectangular columns 600x250.		271	m2	120.00	32,520
	Reinforcement in Columns (200kg/m3)		5	t	2,800.00	14,000
	Concrete in Columns		24	m3	282.00	6,768
	Columns Grd Floor (2.8)					
	Formwork to rectangular columns 600x250		143	m2	120.00	17,160
	Reinforcement in Columns (200kg/m3)		3	t	2,800.00	8,400
	Concrete in Columns		13	m3	282.00	3,666
	Columns Half Slab (2.8)					
	Formwork to rectangular columns 600x250		253	m2	120.00	30,360
	Reinforcement in Columns (200kg/m3)		5	t	2,800.00	14,000
	Concrete in Columns		23	m3	282.00	6,486
	Columns Level 2 (2.8)					
	Formwork to rectangular columns 600x250		396	m2	120.00	47,520
	Reinforcement in Columns (200kg/m3)		7	t	2,800.00	19,600
	Concrete in Columns		35	m3	282.00	9,870
	Columns	<u>'</u>			· ·	
Susper	nded Slab (3 levels Only)					
	Suspended Half Slab Level 1					
	Formwork to soffit of suspended slab and beams		2,580	m2	100.00	257,967
	Formwork to edge of slab perimeter		292	m	43.00	12,561

Trade Detail

Project: Car Park Construction Building: Nowra Car Park	Details:	Details: Nowra Car PArk -3 levels w/o cladding Option 4				
Code Description		Quantity	Unit	Rate	Subtotal	
Suspended Slab (3 levels Only)					(Continued,	
Reinforcement in slabs and beams (250kg/m3)		209	t	2,800.00	585,200	
Concrete to slab and beams		836	m3	260.00	217,360	
Finish and cure slab		2,580	m2	10.00	25,797	
Suspended Slab Level 2						
Formwork to soffit of slab and beams		4,481	m2	100.00	448,126	
Formwork face of beam and edge of slab		292	m	43.00	12,561	
Reinforcement in slabs and beams (250kg/m3)		276	t	2,800.00	773,500	
Concrete to slab and beams		1,105		260.00	287,300	
Finish and cure slab		4,481		10.00	44,813	
Suspended Slab Level 3						
Formwork to soffit of slab and beams		4,481	m2	100.00	448,126	
Formwork face of beam and edge of slab		292	m	43.00	12,561	
Reinforcement in slabs and beams (250kg/m3)		276	t	2,800.00	773,500	
Concrete to slab and beams		1,105		260.00	287,300	
Finish and cure slab		4,481		10.00	44,813	
Suspended Slab (3 levels Only)						
Staircases			1			
Formwork to stairs /perimeter wall		865	m2	100.00	86,500	
Concrete to Stairs /perimeter wall		188	m3	300.00	56,400	
Reinforcement to staircase		22	t	2,800.00	62,115	
Balustrades		50	m	162.00	8,100	
Aluminium Canopy to stairwell roof .		52	m2	250.00	13,000	
Staircases						
Ramps Grd to Level 3			ı			
Ramp Grd to Level 4						
Formwork to ramps		359	m2	100.00	35,900	
Reinforcement to ramps		18	t	2,800.00	50,400	
Concrete to ramps		72	m3	300.00	21,600	
Finish and cure ramps		359	m2	10.00	3,590	
Ramps Grd to Level 3						
Perimeter Crash Barrier			<u> </u>			
Crash Barrier		853	m	200.00	170,600	
Perimeter Crash Barrier			•	<u>'</u>		
Doors						


CostX Turner & Townsend Page 2 of 3 8/06/2012 9:48:55 AM

Trade Detail

Project: Car Park Construction Building: Nowra Car Park Deta			ails: Nowra Car PArk -3 levels w/o cladding Option 4			
Code	Description		Quantity	Unit	Rate	Subtotal
Doors						(Continued)
	Solid core doors inclusive of hardware for eatrances into srairwell		12	no	800.00	9,600
	Doors					
Vall F	inishes					
	Paint to Liftwell walls		297	m2	15.00	4,455
	Wall Finishes					
loor	Finishes					
	Line markings		11,543	m2	5.00	57,715
	Sealer and paint to concrete floor		11,543	m2	8.00	92,344
	Floor Finishes					
itmer	nts					
	Wheel Stops		365	no	350.00	127,750
	Sundry carpark fitments and signage		1	item	20,000.00	20,000
	Fitments					
Electri	ic Lighting					
	Top floor lighting		1	item	75,000.00	75,000
	Lighting Grd , Level 2, Level 3		2	item	28,000.00	56,000
	Lighting Half Suspended Floor		1	item	15,600.00	15,600
	Electric Lighting					
Power	Supply					
	Power Supply and distribution		1	item	40,000.00	40,000
	Power Supply					
Extern	nal Concrete Path					
	External conc Path (1m wide)		210	m	250.00	52,500


External Concrete Path

CostX Turner & Townsend Page 3 of 3




PARKING SPACES SCHEDULE- OPTION 1				
TAG	COUNT	DESCRIPTION		
LEVEL (SFL			
PK1	64	STANDARD 90° USER CLASS 3 PARKING SPACE		
PK5	8	DISABLED PARKING SPACE		
LEVEL C	SFL: 72			
LEVEL 1	SFL			
PK1	140	STANDARD 90° USER CLASS 3 PARKING SPACE		
PK5	7	DISABLED PARKING SPACE		
LEVEL 1	SFL: 147			
LEVEL 2	2 SFL			
PK1	152	STANDARD 90° USER CLASS 3 PARKING SPACE		
LEVEL 2	SFL: 152			
LEVEL 3	SFL			
PK1	152	STANDARD 90° USER CLASS 3 PARKING SPACE		
LEVEL 3	SFL: 152			
LEVEL 4	l SFL			
PK1	152	STANDARD 90° USER CLASS 3 PARKING SPACE		
LEVEL 4	SFL: 152			
Grand t	otal: 675			

CARPARK AREA SCHEDULE			
NAME	AREA		
GROUND AREA	2510.87 m ²		
LEVEL 1	4394.34 m²		
LEVEL 2	4394.34 m²		
LEVEL 3	4394.34 m²		
LEVEL 4	4394.34 m²		
	20088.22 m²		




WORRIGEE STREET CAR PARK







CARPARK PLAN - LEVEL G- OPTION 1




CARPARK PLAN - LEVEL 1 - OPTION 1




WORRIGEE STREET CAR PARK



3D SECTION SCALE







NORTH SOUTH BUILDING SECTION- OPTION 1




WORRIGEE STREET CAR PARK




NORTH ELEVATION



SOUTH ELEVATION



EAST ELEVATION
SCALE 1:250




WEST ELEVATION

WORRIGEE STREET CAR PARK





3D View - Berry St Entry Scale





3D View - Corner Lawrence & Worrigee St

WORRIGEE STREET CAR PARK



3D SECTION OPTION 2





NORTH SOUTH BUILDING SECTION- OPTION 2


23-14263 - SK240



WORRIGEE STREET CAR PARK

V LEVEL 5 SFL

NORTH ELEVATION




SOUTH ELEVATION




23-14263 - SK250




WORRIGEE STREET CAR PARK



EAST ELEVATION
SCALE 1:250



WEST ELEVATION



WORRIGEE STREET CAR PARK



3D View - Berry St Entry OP2



3D View - Corner Lawrence & Worrigee St OP2

WORRIGEE STREET CAR PARK