

SITE SPECIFIC – SAFE WORK METHOD STATEMENT

Notes:

- Work must be performed in accordance with this SWMS.
- This SWMS must be kept and be available for inspection until the high risk construction work to which this SWMS relates is completed.
- If the SWMS is revised, all versions should be kept.
- If a notifiable incident occurs in relation to the high risk construction work in the SWMS, the SWMS must be kept for at least 2 years from the date of the notifiable incident

Work Activity: (Job Description)	Working with non-friable (bonded) Asbestos		Workplace location:	
High Risk Work <i>Indicate if any of the HIGH risk activities are performed by workers</i>	<input type="checkbox"/> is carried out in or near a shaft or trench with an excavated depth greater than 1.5 metres, or tunnel	<input type="checkbox"/> work carried out in or near water or other liquid that involves a risk of drowning	<input type="checkbox"/> Work involving structural alterations or repairs that require temporary support to prevent collapse	
	<input type="checkbox"/> Risk of a person falling more than 2 metres (<i>note: in some jurisdictions this is 3 metres.</i>)	<input type="checkbox"/> work carried out in or near a confined space	<input type="checkbox"/> work carried out on or near pressurised gas distribution mains or piping	
	<input type="checkbox"/> work carried out on or near energised electrical installations or services	<input type="checkbox"/> Involves, or is likely to involve, the disturbance of asbestos	<input type="checkbox"/> work carried out on or near chemical, fuel or refrigerant lines	
	<input type="checkbox"/> Work in an area with movement of powered mobile plant		<input type="checkbox"/> work carried out in an area that may have a contaminated or flammable atmosphere	
	<input type="checkbox"/> Work on, in or adjacent to a road, or other traffic corridor in use by traffic other than pedestrians	<input type="checkbox"/> Work involving demolition of an element of a structure that is load-bearing or otherwise related to the physical integrity of the structure	<input type="checkbox"/> work is carried out on a telecommunication tower	
Person responsible for ensuring compliance with Site Specific SWMS:	Supervisor:		Date Completed	
What measures are in place to ensure compliance with the SWMS?	Compliance with SWMS Site Inspections by Supervisor			
Authorised by:	Name and signature:		Date:	

Note: The following Permits (P20.F03) must be completed in conjunction with this SWMS document (if applicable):

<input type="checkbox"/> Excavation & Trenches Permit	<input type="checkbox"/> Working at Heights Permit
<input type="checkbox"/> Working Near Overhead Powerlines Permit	<input type="checkbox"/> Construction Permit
<input type="checkbox"/> Roadworks Permit	<input type="checkbox"/> Hot Works Permit
<input type="checkbox"/> Plant Permit	<input type="checkbox"/> Work in or near water or other liquid Permit

*SWMS are to be reviewed as per the Document Control Procedure or when there has been a change to the Task / Process or Legislation

What are the tasks involved?	What are the hazards and risks?	What are the control measures?
List the work tasks in logical order.	Identify the hazards and risks that may cause harm to workers or the public.	Describe what will be done to control the risk. What will you do to make the activity as safe as possible?
Step 1. Planning	Multiple hazards	Trained and Competent Workers Ensure removal of <10m2 Non-friable asbestos undertaking by competent trained person. Ensure removal of >10m2 Non-friable asbestos undertaking by person with Asbestos (B class License). Where possible complete a thorough site inspection prior to starting works Asbestos removal control plan Site asbestos register/ asbestos management plan.
Step 2. Site Set Up	Multiple Hazards	Assess site for hazards specific to site Complete Site-Specific Risk Assessment Complete Site-Specific SWMS P20.F03 High Risk Work Permit Book completed for task – <i>Working At Heights</i> <i>Roadworks / Traffic</i> if required. Complete Pre-Start Toolbox Talk All SCC workers and Subcontractors signed on and inducted to the site
EMERGENCY PROCEDURES	Multiple Hazards: Environmental Contamination Respiratory Illness Exposure to asbestos fibers	<u>Prior to starting removal of non-friable asbestos:</u> Provide Emergency Response procedure Have a written rescue plan. Supply an Asbestos Response Kit
	Unauthorised Access Injury to workers Injury to Public Traffic	Isolate work area for 5m distance if possible. Erect Safety Barriers / Warning Tape / Signage to warn of Asbestos Removal work in progress Set-up TCP if required
Step 3. Removal of Non-friable Asbestos	Asbestos / ACM	Licensed asbestos removalist must supply a copy of their asbestos removal control plan to the person who commissioned the licensed asbestos removal work- SCC. Do not use: a. High pressure water spray

What are the tasks involved?	What are the hazards and risks?	What are the control measures?
List the work tasks in logical order.	Identify the hazards and risks that may cause harm to workers or the public.	Describe what will be done to control the risk. What will you do to make the activity as safe as possible?
		b. Compressed air; and - Power tools - Brooms - Any other implements that cause the release of airborne asbestos into the atmosphere. Note: exception applies (excluding a & b above), must be in accordance with C 446 of Regulation and authorised by a Council Officer. <ul style="list-style-type: none"> If tools are required to remove asbestos - manually operated (non-powered) hand tools should be used wherever possible.
	Asbestos Dust (ACD)	Do not generate dust - Use non-powered tools - Dampen/wet down material - Use industrial vacuum fitted with HEPA filter
	Confined/Controlled or Restrictive Space	<ul style="list-style-type: none"> Ensure good ventilation Only remove asbestos in a confined space where it is not possible to avoid working in the confined space. Confined spaces <ul style="list-style-type: none"> - ensure workers CS trained -complete CS permit, -undertake atmosphere testing prior to entry, -provide a Standby Person
	Electricity	<ul style="list-style-type: none"> Where it is required- locate/ de-energise and removing electrical equipment/cables from the asbestos removal work area by a competent person i.e. licensed electrician. Where it is required- locate /positively isolate/ tag-out electrical energy from the asbestos removal work area by competent person i.e. licensed electrician.
	Multiple Hazards	<ul style="list-style-type: none"> Wherever possible, dry asbestos should not be worked on. Prevent or minimise the generation of airborne asbestos fibres i.e. wetting of asbestos using surfactants or wetting agents e.g. PVA glue. Performing the task in a controlled environment e.g. ventilated enclosure.

What are the tasks involved?	What are the hazards and risks?	What are the control measures?
List the work tasks in logical order.	Identify the hazards and risks that may cause harm to workers or the public.	Describe what will be done to control the risk. What will you do to make the activity as safe as possible?
<p>Step 4. De-Establish Site -Decontamination of work area and plant / items used.</p>	<p>Asbestos contamination Exposure to Asbestos Fibres Environmental Contamination Respiratory Illness</p>	<p>Decontaminate - workers, PPE, tools and items used in asbestos removal work.</p> <p>Dry decontamination Seal Asbestos and used PPE in 200 micro-metre plastic double wrapped sheeting, seal with tape should only be used where the `wet method` is not suitable or poses a risk from hazards e.g. electricity.</p> <p>Wet method Wipe down with damp rags. Dampen down material. Use disposable 200 micro-metre plastic drop sheets where debris collected.</p>
<p>5. Asbestos Transport /Disposal</p>	<p>Transportation of asbestos/ACM</p>	<ul style="list-style-type: none"> • The transport ACM must be securely packaged during its transportation and the waste is covered and leak-proof. • If loading directly to a skip bin or truck, the internal surface is to be lined with 2 layers of 200 micro-metre plastic. • Transport to approved waste facility. • Contact a licensed waste depot 24 hours prior to delivering asbestos. • Comply with C-79 Reporting on Transportation of Asbestos Waste requirements of the `Protection of the Environment Operations (Waste) Regulation 2014` for over 100kg or 10m2 of asbestos disposal.
<p>6. Clearance Inspection & or Clearance Certificate before work area is reoccupied for ordinary use.</p>	<p>Asbestos contamination</p>	<ul style="list-style-type: none"> • Removal of <10 m2 of non-friable asbestos- a competent person to undertake a Clearance Inspection and ensure the work site and the immediately surrounding it are free from visible asbestos contamination. • Removal more than 10 m2 of non-friable asbestos a Clearance Inspection be carried out and a Clearance Certificate in writing is required by independent competent person before the workplace is re-occupied. • If air monitoring was carried out, details of the air monitoring results to be recorded in the written Clearance Certificate.

LIKELIHOOD How likely is it to happen? ↓	E=EXTREME H=HIGH M=MEDIUM L=LOW ← CONSEQUENCES – How severely could it affect health and safety? →				
	CATASTROPHIC Kill or cause Permanent Disability	MAJOR Serious Illness or Injury	MODERATE Medical Attention, Time off Work	MINOR First Aid Required	INSIGNIFICANT No Injuries
	ALMOST CERTAIN Is expected to occur	E	E	H	H
LIKELY Will probably occur	E	H	H	M	M
POSSIBLE Might occur	H	H	H	M	L
UNLIKELY Could occur	H	M	M	L	L
RARE May occur only in exceptional circumstances	H	M	M	L	L

Risk Level	Required Action
Extreme	Act immediately: The proposed task or process activity must not proceed. Steps must be taken to lower the risk level to as low as reasonably practicable using the hierarchy of controls.
High	Act today: The proposed activity can only proceed, provided that: The risk level has been reduced to as low as reasonably practicable using the hierarchy of controls. The risk controls must include those identified in legislation, Australian Standards, Codes of Practice etc. and The document has been reviewed and approved by the supervisor and A Safe Working Procedure or Safe Work Method has been prepared and The supervisor must review and document the effectiveness of the implemented risk controls
Medium	Act this week: The proposed task or process can proceed, provided that (i) The risk level has been reduced to as low as reasonably practicable using the hierarchy of controls and The document has been reviewed and approved by the supervisor and A Safe Working Procedure or Safe Work Method has been prepared.
Low	Act this month: Managed by local documented routine procedures which must include application of the hierarchy of controls.

