PROPOSED PEDESTRIAN REFUGE ELIZABETH DRIVE/FREDERICK STREET, VINCENTIA



SHEET INDEX

DRAWING No.	SCC REF. No.	DESCRIPTION
2156-C200	1529.XX	TITLE SHEET
2156-C201	1529.XX	SURVEY AND SERVICES PLAN
2156-C202	1529.XX	SGD11 PLAN AND SCHEDULE
2156-C203	1529.XX	EROSION AND SEDIMENT CONTROL PRINCIPLES PLAN
2156-C204	1529.XX	GENERAL ARRANGEMENT AND SIGNAGE AND LINEMARKING PLAN
2156-C205	1529.XX	KERB PLANS AND LONGITUDINAL SECTION
2156-C206	1529.XX	MK01 CROSS SECTIONS
2156-C207	1529.XX	CONSTRUCTION DETAILS

GENERAL NOTES:

- READ THESE NOTES IN CONJUNCTION WITH OTHER ENGINEERING DRAWINGS AND SPECIFICATIONS, AND WITH SUCH OTHER WRITTEN INSTRUCTIONS ISSUED. REFER TO CIVIL DRAWINGS FOR SETTING OUT AND DETAILED DIMENSIONS. REFER ANY DISCREPANCIES BETWEEN DOCUMENTATION TO SUPERINTENDENT BEFORE PROCEEDING WITH WORK.
- SUBMIT DETAILS OF CHANGES TO SCOPE, WORK METHODS OR MATERIALS ETC FOR APPROVAL BEFORE PROCEEDING. APPROVAL DOES NOT AUTHORISE A VARIATION TO THE CONTRACT.
- 3. NOMINATION OF PROPRIETARY ITEMS DOES NOT INDICATE EXCLUSIVE PREFERENCE, BUT INDICATES REQUIRED PROPERTIES OF THE ITEM. SIMILAR ALTERNATIVES HAVING THE REQUIRED PROPERTIES MAY BE OFFERED FOR APPROVAL. APPROVAL DOES NOT AUTHORISE A VARIATION TO THE CONTRACT. INSTALL PROPRIETARY ITEMS IN ACCORDANCE WITH MANUFACTURERS REQUIREMENTS AND RECOMMENDATIONS.
- 4. DO NOT OBTAIN DIMENSIONS BY SCALING FROM DRAWING.
- 5. DIMENSIONS ARE IN METRES, LEVELS ARE IN METRES UNO, CHAINAGE ARE IN METRES UNO.
- 6. MAINTAIN STRUCTURES IN A STABLE CONDITION DURING CONSTRUCTION AND PROVIDE TEMPORARY BRACING AND/OR SUPPORT AS REQUIRED. PROVIDE SPREADERS AT LOADS AND/OR LIFTING POINTS WHERE REQUIRED. ENSURE NO PART IS OVERSTRESSED. DO NOT PLACE OR STORE BUILDING MATERIALS ON STRUCTURAL MEMBERS WITHOUT SUPERINTENDENTS APPROVAL. PROVIDE CALCULATIONS TO PROVE ADEQUACY OF STRUCTURE FOR PROPOSED CONSTRUCTION METHOD AND LOADS.
- 7. UNLESS NOTED OTHERWISE THESE DRAWING DO NOT DETAIL TEMPORARY WORKS. CONSTRUCTION METHODS AND TEMPORARY WORK ARE RESPONSIBILITY OF THE CONTRACTOR.
- 8. OBTAIN REQUIREMENTS FOR ADJOINING ELEMENTS TO BE FIXED TO OR SUPPORTED ON WORK AND PROVIDE FOR REQUIRED FIXINGS. DRAWINGS DO NOT SHOW DETAILS OF ALL FIXTURES, INSERTS, SLEEVES, RECESSES OR OPENINGS ETC REQUIRED. PROVIDE FOR TEMPORARY SUPPORT OF ADJOINING ELEMENTS DURING CONSTRUCTION.
- 9. WHERE NEW WORK ABUTS EXISTING PROVIDE SMOOTH TRANSITION FREE OF ABRUPT CHANGES.
- 10. BUILD FABRICATE AND PROCURE ONLY FROM DRAWING 'ISSUED FOR CONSTRUCTION'.

1	FOR 80% DESIGN APPROVAL	29/06/22
ISSUE	DESCRIPTION	DATE

FOR DESIGN APPROVAL NOT FOR CONSTRUCTION

FOOTPRINT (NSW) PTY. LTD. AUTHORISE THE USE OF THIS DRAWING ONLY FOR THE PURPOSE DEMONSTRATED BY THE STATUS STAMP SHOWN ABOVE. SCALES

SURVEYOR:KEATLEY

DATUM: AHD

AZIMUTH: MGA2020

DRAWN: AB

DESIGNED: AB

DESIGNED DATE: JUN 2022

CHECKED: AB




PROPOSED PEDESTRIAN REFUGE ELIZABETH DRIVE/FREDERICK STREET, VINCENTIA


2156-C200
ISSUE.

1
SHEET 1 OF 8

City Council Sco PLAN REFERENCE

TITLE SHEET





Phase 1 - Investigation Field Audit Phase 2 - Proposed Impact Phase 3 - Work As Executed Project SCIMS Origin Comments Class PU LU Mark ID Mark ID Northing Zone Coord Source 6115543.999 56 Calculated RL Class PU LU Datum Easting Mark Status Project Impact Inspection Date Not Found Already Gone 289393.118 Found Intact 1931 DP216860 D42020 289405.324 6115526.767 56 Found Intac 14/02/2022 Found Intact 6115536.73 56 1932 SS13980 SSM SCIMS 5DA2020 289413.463 SCIMS 0.03 0.03 29.096 0.12 0.04 Found Intact 14/02/2022 Already Gone DP203169 289433.495 6115520.075 56 Calculated 14/02/2022 Destroyed 1934 1935 GIP DP28174 DA2020 289454.445 6115554.632 56 Traverse Found Intac 14/02/2022 Found Intact Safe Not Found | Already Gone DP28172 3DA2020 289412.729 6115560.575 56 Calculated Not Found 14/02/2022 289450.723 Found Intact 1937 DHW UNKNOWN 5DA2020 289444 953 6115609.539 56 Traverse Found Intact 14/02/2022 1938 GIP DP620101 GDA2020 289458.987 6115627.119 56 Traverse Found Intact 14/02/2022


SURVEY MARK PROTECTION:

- 1. IN ACCORDANCE WITH SECTION 24(1) OF THE SURVEYING AND SPATIAL INFORMATION ACT 2002 A PERSON MUST NOT REMOVE, DAMAGE, DESTROY, DISPLACE, OBLITERATE OR DEFACE ANY SURVEY MARK UNLESS AUTHORISED TO DO SO BY THE SURVEYOR GENERAL. IN THIS REGARD ANY PROPOSED CONSTRUCTION WORK THAT MAY AFFECT A STATE SURVEY MARK CANNOT BE UNDERTAKEN UNTIL A REGISTERED SURVEYOR IS ENGAGED TO ARRANGE ITS RELOCATION, IN ACCORDANCE WITH THE REQUIREMENTS OF THE NSW GOVERNMENT LAND AND PROPERTY INFORMATION.
- 2. REFER TO SURVEY MARK AUDIT SCHEDULE FOR IMPACTED MARKS
- THE CONTRACTOR SHALL AT ALL TIMES BE RESPONSIBLE TO THE PROTECTION OF EXISTING SURVEY MARKS IN ACCORDANCE WITH THE REQUIREMENTS OF ANY PRESERVATION OF SURVEY INFRASTRUCTURE STRATEGY REPORT AND SPATIAL SERVICES CONDITIONAL APPROVAL.

1	FOR 80% DESIGN APPROVAL	29/06/22
ISSUE	DESCRIPTION	DATE

FOR DESIGN APPROVAL NOT FOR CONSTRUCTION

FOOTPRINT (NSW) PTY. LTD. AUTHORISE THE USE OF THIS DRAWING ONLY FOR THE PURPOSE DEMONSTRATED BY THE STATUS STAMP SHOWN ABOVE.





PROPOSED PEDESTRIAN REFUGE

ELIZABETH DRIVE/FREDERICK STREET, VINCENTIA

SGD11 PLAN AND SCHEDULE

DRAWING NO.	·=
2156-C202	Council
ISSUE.	3 ×
1	Ü
SHEET 3 OF 8	T

1529.XX

GENERAL REQUIREMENTS

THE FOLLOWING EROSION AND SEDIMENT CONTROL PLAN (ESCP) HAS BEEN DEVELOPED IN GENERAL ACCORDANCE WITH LANDCOM (2004) — MANAGING URBAN STORMWATER: SOILS AND CONSTRUCTION, OTHERWISE KNOWN AS "THE BLUE BOOK". THE CONTRACTOR SHALL BE AT ALL TIMES RESPONSIBLE FOR TAILORING THE EROSION AND SEDIMENT CONTROL PLAN TO SUIT SITE CONDITIONS. AS CONSTRUCTION PROGRESSES THE CONTRACTOR SHALL AMEND THE EROSION AND SEDIMENT CONTROL PLAN ACCORDINGLY. IT IS THE CONTRACTOR'S RESPONSIBILITY ALL TIMES TO ENSURE THAT THE EROSION AND SEDIMENT MANAGEMENT MEASURES COMPLY WITH THE REQUIREMENTS OF THE BLUE BOOK.

SITE ESTABLISHMENT

PRIOR TO THE COMMENCEMENT OF EARTHWORKS ON THE SITE THE FOLLOWING SHALL BE UNDERTAKEN AS

- ERECT SAFETY FENCING WITH SIGNAGE CLEARLY INDICATING THAT THE SITE IS A CONSTRUCTION ZONE AND ACCESS IS RESTRICTED AS DEEMED NECESSARY.

 ERECT CLEARLY VISIBLE BARRIER FENCING AT LOCATIONS SHOWN OR IF NOT SHOWN AT THE DISCRETION OF THE SITE SUPERINTENDENT TO ENSURE TRAFFIC IS CONTROLLED AND TO PROHIBIT UNNECESSARY SITE DISTURBANCE.

 INSTALL STABILISED SITE ACCESS IN ACCORDANCE WITH STANDARD DRAWING SD6—14 AT EACH SITE ACCESS POINT TO PREVENT CONSTRUCTION EQUIPMENT FROM CARRYING SEDIMENT OFF THE SITE ONTO SURROUNDING ROADS AS REQUIRED.

 INSTALL SEDIMENT AND EROSION CONTROL DEVICES IN ACCORDANCE WITH THE CONSTRUCTION DETAILS SPECIFIED IN THIS DRAWING SET AND/OR THE REQUIREMENTS OF THE 'BLUE BOOK'.

- CONSTRUCTION

 5. TOPSOIL, FROM ALL AREAS TO BE DISTURBED, SHALL BE STRIPPED PRIOR TO CONSTRUCTION OF ANY WORKS AND STOCKPILED AND LATER RESPREAD TO AID REVEGETATION IN LOCATIONS WHERE SHOWN ON THIS DRAWING. TOPSOIL SHALL BE STOCKPILED IN WINDROWS OUTSIDE OF MAJOR FLOW AREAS.

 6. ALL DRAINAGE WORKS SHALL BE CONSTRUCTED AND STABILISED AS EARLY AS POSSIBLE DURING

- ALL DRAINAGE WORKS SHALL BE CONSTRUCTED AND STABILISED AS EARLY AS POSSIBLE DURING DEVELOPMENT.

 ALL TAIL—OUT DRAINS SHALL BE GRASSED AND TRAPEZOIDAL IN SECTION. HAY BALES SHALL BE PLACED AS A SEDIMENTATION CONTROL DEVICE WHERE REQUIRED.

 ALL DISTURBED AREAS SHALL BE REVEGETATED AS SOON AS THE RELEVANT WORKS ARE COMPLETED. TOPSOIL SHALL BE AMELIDRATED AND COMPOSTED TO LANDSCAPE ARCHITECTS SPECIFICATIONS. INLET FILTERS WILL BE INSTALLED WHERE SHOWN TO PREVENT WATER FROM DIRECTLY ENTERING THE PERMANENT DRAINAGE SYSTEM UNLESS IT IS RELATIVELY SEDIMENT FREE. IF THE LOCATION OF INLET FILTERS ARE NOT SHOWN ON THE PLAN THEIR LOCATION SHALL BE AT THE DISCRETION OF THE SUPERINTENDENT.

STOCKPILES

- OCKPILES

 SPOIL AND TOPSOIL STOCKPILES SHALL BE LOCATED NO CLOSER THAN 5m FROM EXISTING VEGETATION, CONCENTRATED WATER FLOW, ROADS AND HAZARD AREAS.

 IF STOCKPILES ARE TO BE IN PLACE FOR LONGER THAN 10 DAYS THEN THEY SHALL BE STABILISED BY COVERING WITH MULDH OR WITH TEMPORARY VEGETATION.

 STOCKPILES SHALL BE IN WINDROWS NO HIGHER THAN 2m HIGH AND SHALL HAVE BATTER SLOPES NO STEEPER THAN 1 IN 2. AN EARTH BANK SHALL BE INSTALLED ON THE UPSLOPE SIDE AND SEDIMENT FENCING SHALL BE INSTALLED ALONG THE LENGTH OF THE DOWNSLOPE SIDE ON ANY STOCKPILE.

- MAINTENANCE

 13. ALL SEDIMENT BASINS AND TRAPS SHALL BE CLEANED WHEN THE STRUCTURES ARE A MAXIMUM OF ALL SEDIMENT BASINS AND TRAPS SHALL BE CLEANED WHEN THE STRUCTURES ARE A MAXIMOM OF 60% FULL OF SOLID MATERIALS (INCLUDING DURING THE MAINTENANCE PERIOD) AND DISPOSED OF IN A MANNER THAT PREVENTS FURTHER POLLUTION OF THE SITE.

 TEMPORARY SEDIMENT AND EROSION CONTROL DEVICES WILL BE RETAINED UNTIL AFTER THE LANDS THEY ARE PROTECTING, ARE COMPLETELY REHABILITATED.

 THE CONTRACTOR WILL INSPECT THE SITE AT LEAST WEEKLY OR AFTER ANY STORM EVENT AND WILL:

 — ENSURE THAT DRAINS OPERATE PROPERLY AND TO EFFECT ANY NECESSARY REPAIRS;

- ENSURE THAT DRAINS OPERATE PROPERLY AND TO EFFECT ANY NECESSARY REPAIRS;
 REMOVE SPILLED SAND OR OTHER MATERIALS FROM HAZARD AREAS (E.G. LANDS CLOSER THAN FIVE METRES FROM AREAS OF LIKELY CONCENTRATED OR HIGH VELOCITY FLOWS ESPECIALLY DRAINS, WATERWAYS AND PAVED AREAS);
 REMOVE TRAPPED SEDIMENT WHENEVER LESS THAN DESIGN CAPACITY REMAINS WITHIN THE STRUCTURE;
 ENSURE REHABILITATED LANDS HAVE EFFECTIVELY REDUCED THE EROSION HAZARD AND TO INITIATE UPGRADING OR REPAIR AS APPROPRIATE;
 CONSTRUCT ADDITIONAL EROSION AND/OR SEDIMENT CONTROL WORKS AS REQUIRED;
 MAINTAIN EROSION AND SEDIMENT CONTROL MEASURES IN A FULLY FUNCTIONING CONDITION UNTIL ALL EARTHWORK ACTIVITIES ARE COMPLETED AND THE SITE IS REHABILITATED; AND
 REMOVE TEMPORARY EROSION AND SEDIMENT CONTROL STRUCTURES AS THE LAST ACTIVITY IN THE REHABILITATION PROGRAM.

 A SELF-AUDITING PROGRAM WILL BE ESTABLISHED BASED ON A CHECK SHEET. A SITE INSPECTION USING THE CHECK SHEET WILL BE MADE BY THE CONTRACTOR:

 AT LEAST WEEKLY;


- - AT LEAST WEEKLY:


 - AT LEAST WEEKLY;
 IMMEDIATELY BEFORE SITE CLOSURE;
 IMMEDIATELY BEFORE FORECAST RAIN AND AFTER RAINFALL.
 ENTRIES WILL INCLUDE (BUT ARE NOT LIMITED TO):


 a. THE VOLUME AND INTENSITY OF ANY RAINFALL EVENTS;
 b. THE CONDITION AND MAINTENANCE OF ANY SOIL AND WATER MANAGEMENT PLAN WORKS;
 c. THE CONDITION OF VEGETATION AND ANY NEED TO IRRIGATE;
 d. THE NEED FOR DUST PREVENTION STRATEGIES; AND
 e. ANY REMEDIAL WORKS TO BE UNDERTAKEN.
 A SIGNED DUPLICATE OF THE CHECK SHEET SHOULD BE FORWARDED TO THE PROJECT MANAGER
 WEEKLY FOR THEIR INFORMATION. ALL CHECK SHEETS SHOULD BE COLLATED, KEPT ON—SITE
 AND MADE AVAILABLE TO ANY AUTHORISED PERSON ON REQUEST.

- SEQUENCE OF WORKS:

 1 INISTALL SOIL AND WATER MANAGEMENT MEASURES AS DETAILED.
- REMOVE MANAGEMENT DEVICES ON SUCCESSFUL REHABILITATION.









1	FOR 80% DESIGN APPROVAL	29/06/22	
ISSUE	DESCRIPTION	DATE	

FOR DESIGN APPROVAL NOT FOR CONSTRUCTION

FOOTPRINT (NSW) PTY, LTD, AUTHORISE THE USE OF THIS

SCALES	SURVEYOR:KEATLEY		
	DATUM: AHD		
AS NOTED	AZIMUTH: MGA2020		
ORIGINAL	DRAWN: AB		
URIGINAL	DESIGNED: AB	1	
A1	DESIGNED DATE: JUN 2022		
,,,	CHECKED: AB	1	
			-




PROPOSED PEDESTRIAN REFUGE


ELIZABETH DRIVE/FREDERICK STREET, VINCENTIA


EROSION AND SEDIMENT CONTROL PRINCIPLES PLAN

DRAWING NO.	177
2156-C203	9
ISSUE.	3
1	
HEET 4 OF 8	T

1529 XX







1	FOR 80% DESIGN APPROVAL	29/06/22
ISSUE	DESCRIPTION	DATE

FOR DESIGN APPROVAL NOT FOR CONSTRUCTION

FOOTPRINT (NSW) PTY. LTD. AUTHORISE THE USE OF THIS DRAWING ONLY FOR THE PURPOSE DEMONSTRATED BY THE STATUS STAMP SHOWN ABOVE.

SCALES	SURVEYOR:KEATLEY	
	DATUM: AHD	
AS NOTED	AZIMUTH: MGA2020	
0.000.00	DRAWN: AB	
ORIGINAL	DESIGNED: AB	
A1	DESIGNED DATE: JUN 2022	
, , ,	CHECKED: AB	




PROPOSED PEDESTRIAN REFUGE

ELIZABETH DRIVE/FREDERICK STREET, VINCENTIA

MK01 CROSS SECTIONS


DRAWING NO.	ji.	
2151-C206	Council	, ×
ISSUE.	\$ 2	ရွိ တွ
1	ξÖ	1529.
SHEET 7 OF 8	1	00 P



150 NOMINAL FACE OF KERB **-**−25


150mm BARRIER KERB AND GUTTER DETAIL

TYPICAL KERB AND GUTTER CONSTRUCTION DETAIL



CONCRETE PATH DETAIL


SAW CUT CONTRACTION JOINT DETAIL



PROVIDE ELASTOMERIC SEALANT TO FILL VOID-LEFT BY KEY CAPPING. 100mm CONNOLLY KEY JOINT (KJ100) -WITH REMOVABLE CAPPING, OR APPROVED EQUIVALENT. INDUCED CRACK AT STOP MESH 50mm FROM KEY, BOTH SIDES.

DOWELLED EXPANSION JOINT DETAIL

KEY CONTRACTION JOINT DETAIL




ISOLATION JOINT DETAIL

STOP MESH 50mm FROM JOINT.

R12 x 500mm LONG GALVANISED DOWELS AT 400mm CENTRES, CAST INTO FIRST POUR. BITUMEN PAINT AND-PROVIDE PLASTIC SLEEVE TO SECOND POUR.


- DOWELLED EXPANSION JOINTS OR KEY JOINTS TO BE PLACED LATERALLY AT INTERVALS NOT EXCEEDING 3 X PATH WIDTH (MAX 12m, 4.5m TYPICAL), REPLACING THE SAW CUT JOINT AT THAT INTERVAL.
- (E.G. BETWEEN NEW SLABS AND EXISTING KERBS, PITS OR DRIVEWAYS).



TYPICAL FOOTPATH WITH INTEGRAL HOB DETAIL


JOINTING NOTES

- SAW CUT JOINTS (I.E. CONTRACTION JOINT) TO BE PLACED PLACED LATERALLY AT INTERVALS NOT EXCEEDING 1 X PATH WIDTH (MAX 4m, 1.5m TYPICAL). SAW CUTS CAN BE SUBSTITUTED WITH KEY JOINTS.
- 3. ISOLATION JOINTS TO BE USED BETWEEN NEW STRUCTURES AND ADJOINING STRUCTURES



FOR DESIGN APPROVAL NOT FOR CONSTRUCTION

FOOTPRINT (NSW) PTY. LTD. AUTHORISE THE USE OF THIS DRAWING ONLY FOR THE PURPOSE DEMONSTRATED BY THE STATUS STAMP SHOWN ABOVE.





FILL VOID OVER BACKING ROD WITH ELASTOMERIC SEALANT. PROTECT TOP OF SLAB WHILE SEALING AND TOOL TOP OF SEALANT WITH ROUNDED SPATULA TOOL.

LAY (1.25W)mm BACKING ROD IN GROOVE, LEAVING A GAP 'D' OF (0.5W)mm TO

ABELFLEX (OR EQUIVALENT) FOR FULL DEPTH OF SLAB.

PROPOSED PEDESTRIAN REFUGE

ELIZABETH DRIVE/FREDERICK STREET, VINCENTIA

CONSTRUCTION DETAILS

DRAWING NO 529 XX 2151-C207 **Ş**Ö ζį SHEET 8 OF 8