

Safe Work Instruction - Truck - Flocon

DO NOT use this plant* or complete this task unless you have been inducted in its safe use and operation by an Authorised Experienced Operator

This SWI may not cover all possible hazards and risks and should be referred to as a control measure in the risk assessment process. Additional training may be required for high risk plant/work. Site and task may change required PPE.

PERSONAL PROTECTIVE EQUIPMENT



Eye protection must be worn



Long and loose hair must be contained or covered.



Protective body clothing must be worn



Foot protection must be worn



Hand protection must be worn



High visibility clothing must worn



Minimum P2 face mask or respirator must be worn when airborne dust or fumes are created



Walk-a-Round

POTENTIAL HAZARDS AND RISKS

- Entanglement**
Entanglement in moving parts
- Manual Task Injury**
Manual task injury from repetitive movements
- Struck by Moving Object**
Struck by moving object due to unexpected movement of plant
- Other**
Injury from contact with moving parts
Contact with hot or cold parts of plants
Injury due to plant malfunction or misuse
Skin irritation due to exposure to hazardous chemicals
Burn injury
- Exposure to High Pressure Fluid**
Injury from exposure to high pressure fluids
- Cutting, Stabbing or Puncturing**
Injury from unexpected movement of plant
- Exposure to Dust/Fumes**
Exposure to Toxic Fumes
Exposure to other emissions released by the plant
- Slip, Trips, Falls**
Slip, trip or fall whilst entering and exiting vehicle
Slip, trip, fall from entry/exit of plant and slippery plant surfaces

PRE-OPERATIONAL SAFETY CHECKS

- ✓ Complete site specific risk assessment
- ✓ Complete the appropriate pre-operational plant checklist
- ✓ Ensure you are familiar with plant operations and controls
- ✓ Ensure that you have the appropriate SDS for Kerosene, Emoleum and Asphaltic Concrete
- ✓ Ensure that guards are fitted, secured and functional in accordance with manufacturers guidelines
- ✓ If traffic control is required, ensure to have the correct traffic control plans in place BEFORE commencement of work
- ✓ Seat belt to be worn

OPERATING PROCEDURES

- ✓ Keep clear of moving plant parts
- ✓ Operate plant to the conditions of the work area
- ✓ Always watch for bystanders when operating plant. Never assume a person is aware of your presence. Stop the machine if people step into the working area of the plant

- ✓ Driver to be alert when reversing plant
- ✓ Use 3 points of contact when entering and exiting plant
- ✓ All steps, ladders, platforms should be kept clean (to prevent slips & falls)
- ✓ Ensure job rotation is carried out on a regular basis
- ✓ Before making adjustments bring plant to a complete standstill and isolate

ENDING OPERATIONS

- ✓ Park plant on even ground
- ✓ Ensure all cleaning procedures are carried out within close proximity to an EMERGENCY SHOWER
- ✓ Allow plant to cool before performing any maintenance, refuelling or cleaning
- ✓ Refuel plant at least 3 metres from combustibles
- ✓ Ensure plant is in good working order and stored in the appropriate location

DO NOT

- ✗ Do not use if plant is faulty. Attach an Out of Service tag and report fault to your supervisor

- ✘ Do not leave plant running unattended
- ✘ Do not overfill tank
- ✘ Do not ride on back of truck
- ✘ Do not put hands on, or in the vicinity of moving conveyor belt
- ✘ Do not leave keys in machinery whilst unattended
- ✘ Do not wear loose jewellery
- ✘ Do not use mobile phone while operating plant

***Plant in this SWI refers to any machinery, equipment, appliance, container, implement and tool.**